c/o Kasselsvlei & Peter Barlow Drive, Kasselsvlei, 7533
PO Box 456, Bellville South, Cape Town
T: +27 (21) 959 8217 F: +27 (86) 767 2374
W: surcotec.co.za

QUT-03-01-01 Rev 1

QUOTATION

Date:	**19/01/2026**
Attention:	**Cleven Lewis**
Company:	**Atlantis Foundries**
Tel number:	**021**
Description:	**160Ø Linear Shaft for HVOF coating**
Quantity:	**2 off**
Client Ref. number:	
Quote number:	**SCT 7725**
Surcotec Ref. Number:	**SD**

Dear Cleven

We thank you for the valued enquiry, and have pleasure in providing our quotation as follows:

SCOPE OF WORK:

To collect from your works
To visually inspect and record nominal dimensions
To pre-machine off all old coating and damage clean and parallel
To build up with Surcotec 1302 Micro Alloys using the ARC spray system
To set up and machine shaft complete 0.3mm undersize
To top coat with Surcotec 3604 Micro Alloys using the HVOF spray system
To final grind to surface finish and tolerances given
To crack test coating integrity
To fettle, hand polish, de-mask, de-burr and clean where necessary
To seal with anaerobic sealers
To final inspect
To deliver to your works

PRICE:

The cost per scope of work is (each and excl. VAT)

- **To repair and recoat Linear shaft** **R116 000.00 ea. Excl. V.A.T**

c/o Kasselsvlei & Peter Barlow Drive, Kasselsvlei, 7533
PO Box 456, Bellville South, Cape Town
T: +27 (21) 959 8217 F: +27 (86) 767 2374
W: surcotec.co.za

Total cost for both Shafts **R232 000.00 Excl. V.A.T**

DELIVERY:

10-15 Working days from order or receipt of goods

i. **The quotation is based on the assumption that the required coating thickness will not be more than 2mm. If after pre-grinding/machining the required coating thickness is more, Surcotec will re-quote.**
ii. **The parts are assumed to be in good condition and should unexpected problems or scope change, be revealed on commencement of work, Surcotec retains the right to re-quote and change delivery date.**

Deviation from "i" and "ii" above may impact on delivery date.

GENERAL:

- All work is performed under TNV certified ISO9001 quality system.
- Payment strictly 7 days from date of invoice for approved accounts. All others strictly C.O.D.
- Quotation is valid for 60 days.
- Surcotec's General Conditions of Contract shall apply to this quotation and any contract resulting from acceptance thereof (Available on request).
- A copy of the quality control plan as per the described scope of work will be issued on request by the customer, if the quality control plan is not requested it is accepted that the scope of work as set out in the quotation is accepted by the customer.

Kind Regards,

Sheldon Deysel
Technical Sales Engineer
083 669 1861