c/o Kasselsvlei & Peter Barlow Drive, Kasselsvlei, 7533
PO Box 456, Bellville South, Cape Town
T: +27 (21) 959 8217 F: +27 (86) 767 2374
W: surcotec.co.za

QUT-03-01-01 Rev 1

QUOTATION

Date:	**11/02/2026**
Attention:	**Quinton**
Company:	**Petec**
Tel number:	**021-5**
Description:	**Winch frame & Gearbox repair**
Quantity:	**As Below**
Client Ref. number:	**Donna Jane**
Quote number:	**SCT 7757**
Surcotec Ref. Number:	**IW**

Dear Quinton,

We thank you for the valued enquiry, and have pleasure in providing our quotation as follows:

SCOPE OF WORK: Frame

- To set up, evaluate, record dimensions and manufacture alignment dollies
- To pre machine bearing bores & reference journals
- To mask and blast
- To build up with SURCOTEC ~~1500~~ 1201 on bearing bores
- To final line bore to specified dimensions on bearing bores and oversize on retainer bores
- To spray and machine retainers due to revised dimension
- To seal with anaerobic sealer
- To final inspect
- To deliver to your works

SCOPE OF WORK: Gearbox

- To set up, evaluate, record dimensions and pre machine 4 x bearing bores
- To mask and blast
- To build up with SURCOTEC ~~1500~~ 1201 on bores
- To final machine to specified dimensions & tolerances
- To seal with anaerobic sealer
- To final inspect
- To deliver to your works

c/o Kasselsvlei & Peter Barlow Drive, Kasselsvlei, 7533
PO Box 456, Bellville South, Cape Town
T: +27 (21) 959 8217 F: +27 (86) 767 2374
W: surcotec.co.za

SCOPE OF WORK: Stub Shaft

- To set up, evaluate, record dimensions and pre machine bearing journal in preparation
- To mask and blast
- To build up with SURCOTEC 1201 on bearing journal (8m/m build up)
- To final grind to specified dimension
- To seal with anaerobic sealer
- To final inspect
- To deliver to your works

PRICE:

The cost per scope of work is (each and excl. VAT)

• **Frame repair**	**R 45'460.00 . Ea Excl. V.A.T**
• **Gearbox repair**	**R 42'285.00 . Ea Excl. V.A.T**
• **Stub shaft repair**	**R 15'520.00 . Ea Excl. V.A.T**
Quotation total ex vat	**R 103'265.00**

DELIVERY:

5 days from order

i. **The parts are assumed to be in good condition and should unexpected problems or scope change, be revealed on commencement of work, Surcotec retains the right to re-quote and change delivery date.**

Deviation from "i" and "ii" above may impact on delivery date.

GENERAL:

- All work is performed under TNV certified ISO9001 quality system.
- Quotation is valid for 60 days.
- Surcotec's General Conditions of Contract shall apply to this quotation and any contract resulting from acceptance thereof (Available on request).
- A copy of the quality control plan as per the described scope of work will be issued on request by the customer, if the quality control plan is not requested it is accepted that the scope of work as set out in the quotation is accepted by the customer.

Kind Regards,

Ian Walsh
Sales and Marketing Manager